FINAL REPORT

DECEMBER 1987

EVT 30-87-1

MIL-STD-1660 TEST OF STANDARD OAK PALLET COMPARISON OF BIG LEAF MAPLE PALLET



Prepared for:

U.S. Army Armament, Munitions and

Chemical Command

ATTN: SMCAR-ESK

Rock Island, IL 61299-7300

Distribution Unlimited

**EVALUATION DIVISION SAVANNA, ILLINOIS 61074-9639** 

89

4

25

US ARMY ARMAMENT MUNITIONS CHEMICAL COMMAND

US ARMY DEFENSE AMMUNITION CENTER AND SCHOOL

033

#### AVAILABILITY NOTICE

A copy of this report is furnished each attendee on automatic distribution.

Additional copies or authority for reprinting may be obtained by written request from Director, U.S. Army Defense Ammunition Center and School.

ATTN: SMCAC-DEV, Savanna, IL 61074-9639.

#### DISTRIBUTION INSTRUCTIONS

Destroy this report when no longer needed. Do not return.

\* \* \*

Citation of trade names in this report does not constitute an official endorsement.

\* \* \*

The information contained herein will not be used for advertising purposes.

REPORT D	OCUMENTATIO	N PAGE			Form Approved OMB No. 0704-0188	
1a. REPORT SECURITY CLASSIFICATION UNCLASSIFIED	16. RESTRICTIVE MARKINGS					
2a. SECURITY CLASSIFICATION AUTHORITY	3. DISTRIBUTION/AVAILABILITY OF REPORT					
2b. DECLASSIFICATION / DOWNGRADING SCHEDU	LE	1				
4. PERFORMING ORGANIZATION REPORT NUMBE EVT 30-87-1	R(S)	5. MONITORING ORGANIZATION REPORT NUMBER(S)				
6a. NAME OF PERFORMING ORGANIZATION U.S. Army Defense Ammunition Center and School	6b. OFFICE SYMBOL (If applicable) SMCAC-DEV	7a NAME OF MONITORING ORGANIZATION U.S. Army Armament, Munitions and Chemical Command				
6c. ADDRESS (City, State, and "P Code) Savanna, IL 61074		7b. ADDRESS (City, State, and ZIP Code) ATTN: SMCAR-ESK Rock Island, IL 61299-7300				
8a. NAME OF FUNDING/SPONSORING ORGANIZATION Same as Block 7a.	8b. OFFICE SYMBOL (If applicable)	9. PROCUREMENT INSTRUMENT IDENTIFICATION NUMBER				
8c. ADDRESS (City, State, and ZIP Code)	<u> </u>	10. SOURCE OF F	UNDING NUMBER	\$		
		PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO.	WORK UNIT ACCESSION NO.	
12. PERSONAL AUTHOR(S) A. C. McIntosh, Jr.  13a. TYPE OF REPORT FINAL FROM TO DECEMBER 1987  15. PAGE COUNT DECEMBER 1987  16. SUPPLEMENTARY NOTATION						
17. COSATI CODES  18. SUBJECT TERMS (Continue on reverse if necessary and identify by block number)  MIL-STD-1660 standard wood pallet  hardwood  MIL-L-15011-J						
The U.S. Army Defense Ammunition Center and School (USADACS), Evaluation Division was tasked by the U.S. Army Armament, Munitions and Chemical Command (AMCCOM), SMCAR-ESK, to evaluate a MIL-P-15011-J type pallet fabricated from West Coast Big Leaf Maple wood. Maple, as determined by the wood industry, is classified as a softwood not meeting the requirements of MIL-P-15011-J requirements for fabrication of ammunition pallets. Oak, however, is a satisfactory hardwood for the fabrication of ammunition pallets. In order to compare the test results of Big Leaf Maple and oak pallets in their performance when subjected to MIL-STD-1660 testing criteria, a second pallet was fabricated identical to the Big Leaf Maple on an oak base. The subject pallet was then tested in accordance with MIL-STD-1660 and found to perform equally as well as the Big Leaf Maple pallet. The results of these tests indicate that oak and Big Leaf Maple perform identically when tested to MIL-STD-1660.						
20. DISTRIBUTION / AVAILABILITY OF ABSTRACT UNCLASSIFIED/UNLIMITED SAME AS RI 22a. NAME OF RESPONSIBLE INDIVIDUAL	PT DTIC USERS	L	CURITY CLASSIFICA ED Include Area Code		FICE SYMBOL	
THOMAS J. MICHELS  DD Form 1473, JUN 86	Previous editions are	AV 585-8928	· · · · · · · · · · · · · · · · · · ·	SMCA	FICE SYMBOL C-DEV	


# U.S. Army Defense Ammunition Center and School Savanna, IL 61073-9429

#### REPORT NO. EVT-30-87-1

#### MIL-STD-1660 TEST OF BIG LEAF MAPLE PALLET

#### TABLE OF CONTENTS

					PAGE
PART	l	-	GENI	ERAL	
			A.	INTRODUCTION	1-1
			В.	AUTHORITY	1-1
			c.	OBJECTIVE	1-1
PART	2	-	LIST	OF ATTENDEES	2-1
PART	3	-	TEST	PROCEDURES	3-1
PART	4	-	TEST	EQUIPMENT	4-1
PART	5	-	TEST	RESULTS	5-1
PART	6	-	CONCI	LUSIONS AND RECOMMENDATIONS	6-1
PART	7	-	PHOTO	OGRAPHS	7-1
PART	8	-	UNIT	IZATION PROCEDURES	8-1





- A. INTRODUCTION. The U.S. Army Defense Ammunition Center and School (USADACS) has been tasked by the U.S. Army Armament, Munitions and Chemical Command (AMCCOM), SMCAR-ESK, to evaluate a softwood pallet fabricated from Big Leaf Maple. This has been done and is documented in Report EVT 30-87, November 1987. As a comparison, an identical load was fabricated on a standard oak pallet and subjected to the same MIL-STD-1660 testing sequence. The results of this test and the previous tests of Big Leaf Maple form a basis of pallet material comparison.
- B. <u>AUTHORITY</u>. This study was conducted in accordance with mission responsibilities delegated by AMCCOM.
- C. OBJECTIVE. The objective of this test is to evaluate a standard oak pallet loaded to a test weight of 4,300 pounds and subjected to MIL-STD-1660 Design Criteria for Ammunition Pallets as a control comparison to the Big Leaf Maple pallet.

#### ATTENDEES

Mr. A. C. McIntosh, Jr. Test Engineer U.S. Army Defense Ammunition Center and School ATTN: SMCAC-DEV

Savanna, IL 61074-9639

AV 585-8989

Mr. David V. Valant Electronics Technician U.S. Army Defense Ammunition Center and School

ATTN: SMCAC-DEV

Savanna, IL 61074-9639

AV 585-8988

#### TEST PROCEDURES

The test procedures outlined in this section are extracted from MIL-STD-1660, Design Criteria for Ammunition Unit Loads dated 8 April 1977. This standard identifies nine steps that a unitized load must undergo if it is considered to be acceptable. These tests are synopsized below:

- 1. STACKING TESTS. The unit load shall be loaded to simulate a stack of identical unit loads stacked 16 feet high, for a period of one hour. This stacking load is simulated by subjecting the unit load to a compression of weight equal to an equivalent 16-foot stacking height. The compression load is calculated in the following manner. The unit load weight is divided by the unit load height in inches and multiplied by 192. The resulting number is the equivalent compressive force of a 16-foot high load.
- 2. REPETITIVE SHOCK TEST. The repetitive shock test shall be conducted in accordance with Method 5019, Federal Standard 101. The test procedure is as follows. The test specimen shall be placed on, but not fastened to, the platform. With the specimen in one position, vibrate the platform at 1/2-inch amplitude (1-inch double amplitude) starting at a frequency of about 3-cycles per second. Steadily increase the frequency until the package leaves the platform. The resonant frequency is achieved when a 1/16-inch thick feeler may be momentarily slid freely between every point on the specimen in contact with the platform at some instance during the cycle or a platform acceleration achieves one plus or minus zero point one G. Midway into the testing period the specimen shall be rotated 90 degrees and the test continued for the duration. If failure occurs, the total time of vibration shall be two hours

- of the specimen is tested in one position; and if tested in more than one position, the total time shall be three hours.
- 3. EDGEWISE DROP TEST. This test shall be conducted by using the procedures of Method 5008, Federal Standard 101. The procedure for the Edgewise Drop (Rotational) Test is as follows: The specimen shall be placed on its bottom with one end of the base of the container supported on a sill nominally 6 inches high. The height of the sill shall be increased if necessary to ensure that there will be no support for the base between the ends of the container when dropping takes place, but should not be high enough to cause the container to slide on the supports when the dropped end is raised for the drops. The unsupported end of the container shall then be raised and allowed to fall freely to the concrete, pavement, or similar underlying surface from a prescribed height. Unless otherwise specified, the height of drop for level A protection shall conform to the following tabulation.

GROSS WEIGHT NOT EXCEEDING	DIMENSIONS ON ANY EDGE NOT EXCEEDING	HEIGHT OF DROP LEVEL A PROTECTION
Pounds	Inches	Inches
600	72	36
3,000	no limit	24
no limit	no limit	12

4. IMPACT TEST. This test shall be conducted by using the procedure of Method 5023, Incline-Impact Test of Federal Standard 101. The procedure for the Incline-Impact Test is as follows:

The specimen shall be placed on the carriage with the surface or edge which is to be impacted projecting at least 2 inches beyond the front end of the carriage. The carriage shall be brought to a predetermined position on the

incline and released. If it is desired to concentrate the impact on any particular position on the container, a 4x4-inch timber may be attached to the bumper in the desired position before the test. No part of the timber shall be struck by the carriage. The position of the container on the carriage and the sequence in which surfaces and edges are subjected to impacts may be at the option of the testing activity and will depend upon the objective of the tests. When the test is to determine satisfactory requirements for a container or pack and unless otherwise specified the specimen shall be subjected to one impact on each surface that has each dimension less than 9.5 feet. Unless otherwise specified, the velocity at time of impact shall be 7 feet per second.

#### TEST EQUIPMENT

#### 1. TEST SPECIMEN.

a. Drawing Number: 19-48-4116/15C

b. Width: 40 inches

c. Length: 48 inches

d. Height: 49 inches

e. Weight: 4,300 pounds

#### 2. COMPRESSION TESTER.

a. Manufacturer:

b. Platform: 60 inches by 60 inches

c. Compression Limit: 50,000 pounds

d. Tension Limit: 50,000 pounds

#### 3. TRANSPORTATION SIMULATOR.

a. Manufacturer: Gaines Laboratory

b. Capacity: 6,000-pound pallet

c. 1/2-inch Amplitude

d. Speed: 50 to 3000 cpm

e. Platform: 5 foot by 8 foot

#### 4. INCLINED RAMP.

a. Manufacturer: Conbur Incline

b. Impact Tester

c. 10% Incline

d. 12-foot Incline

#### TEST\_RESULTS

#### 1. STACKING IST.

Pall: Weight: 4,300 pounds

Pallet Height: 49 inches

Test Load Weight: 17,000 pounds

The subject pallet was loaded to 17,500 pounds compression for a period of one hour. At the end of that period of time, the compression load decreased to 16,200 pounds. When the test specimen was removed from the compression tester, no measurable deformation to the unit load was realized.

#### 2. REPETITIVE SHOCK TEST.

The subject pallet successfully passed the longitudinal transportation test in a 90-minute period. Rotating the pallet 90 degrees and subjecting it to a second 90-minute period in the transportation simulator caused no damage to the pallet or strapping. Operational speed of the transportation simulator for these two tests was 200 rpm. Approximate driving force into the load from the transportation simulator table is .5 G acceleration.

#### 3. EDGEWISE DROP TEST.

Each side of the pallet is placed on a beam in turn displacing it 6 inches above the floor. The opposite side is raised to a height of 24 inches above the floor and then dropped. (The normal drop height for a pallet weighing over 3,000 pounds is 12 inches. The drop height for this test was 24 inches.) Impacts 1 and 3 had the skids oriented laterally to the direction of the drop. In drops 2 and 4, the skids were oriented longitudinal to the direction of drop. The results of the drops 1, 2, and 4 did not cause any damage to the pallet. Drops 1 and 3 caused the outside

skids to crack, but not separate from the pallet base. No damage was caused to the test load.


#### 4. IMPACT TEST.

The inclined impact tests consisted of placing the oak pallet with its 4,0^0-pound unit load on an inclined sled with two inches of the pallet projecting over the edge of the sled. This sled is then raised approximately 8 feet up the inclined ramp and released, allowing it to accelerate and impact into a solid wall. This test was repeated once on each side of the pallet. After completing this test, the pallet was observed to find no additional breaks or damage caused to the unitization.

#### CONCLUSIONS AND RECOMMENDATIONS


- 1. <u>CONCLUSIONS</u>. The oak comparison pallet to the Big Leaf Maple pallet was subjected to MIL-STD-1660 testing procedures for ammunition pallets. The oak pallet was fabricated to MIL-P-15011-J specifications. This pallet performed successfully in satisfying the requirements of design criteria for ammunition unit loads. When dropped in an extended height edgewise rotational drop test, the outer skids cracked. Even though this is damage to the pallet, it is not cause for rejection, since the unitization remained intact and was suitable for safe movement.
- 2. RECOMMENDATIONS. The oak pallet, as tested, is a standard pallet that has been used for many years in transporting ammunition unit loads. This test further verifies that oak, as a hardwood used in fabrication of this pallet, is a satisfactory material and shows, thru identical minimal damage areas, that the Big Leaf Maple pallet, which is categorized as a softwood, compares favorably to oak when used in these applications. The previous test (EVT 30-87) of the Big Leaf Maple pallet compares favorably to the results recorded in this report; however, Big Leaf Maple as a wood species is classified as a softwood. Oak is a wood species that is classified as a hardwood. In order to satisfy the requirements for a hardwood pallet, as per MIL-P-15011-J, Big Leaf Maple must be reclassified as a hardwood or MIL-P-15011-J must identify an exception that this particular species of maple is acceptable for ammunition unit loads. These tests are performed strictly as a performance comparison of the two materials in terms of design criteria for ammunition pallets and not to be used as a basis for reclassifying maple as a hardwood.

#### **PHOTOGRAPHS**



### DEFENSE AMMUNITION CENTER AND SCHOOL - SAVANNA, IL

Photo 1. This photo shows the standard bak pallet loaded with inert-filled M548 cans to a weight of 4,300 pounds.




DEFENSE AMMUNITION CENTER AND SCHOOL- SAVANNA, IL

Photo No. 2. This photo shows the standard oak pallet ready for edgewise rotational crop on side one. Damage sustained in this drop was a cracked outer skid.



LEFEN E AMMUNITON CENTER AND SCHOOL - SAVANNA, IL



## DEFENSE AMMUNITION CENTER AND SCHOOL - SAVANNA, IL

Photo 4. This photo shows the standard oak pallet ready for the edgewise rotational drop on the third side. This drop caused the outer skid to crack.



# DEFENSE AMMUNITION CENTER AND SCHOOL - SAVANNA, IL

Photo 5. This photo shows the standard oak pallet ready for edgewise dropping from a height of 24 inches. No additional damage was caused to the pallet during this drop.



DEFENSE AMMUNITION CENTER AND SCHOOL- SAVANNA, IL



# DEFENSE AMMUNITION CENTER AND SCHOOL - SAVANNA, IL

Photo 8. This photo shows the standard oak pallet after the inclined impact on the third side. No damage was sustained by the pallet or the unitization load.



## DEFENSE AMMUNITION CENTER AND SCHOOL- SAVANNA, IL

Photo 9. This photo shows the standard oak pallet after inclined impact testing on the fourth side. No damage occurred during this impact.

# PART 8 UNITIZATION PROCEDURE

# APPENDIX 15C

# UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

CARTRIDGE, 20MM, PACKED VARIOUS QUANTITIES PER M548 METAL BOX, UNITIZED 24 BOXES PER 40" X 48" PALLET; APPROX BOX SIZE 18 18 L X 8 W X 14 14 H

PALLET UNIT DATA					
CLUDED	HAZ	WEIGHT			
DOD IC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)
A651 A659 A769 A770 A791 A813 A814 A833 A834 A835 A836 A846 A865 A865 A866 A866 A890 A892	C C A A A A A A A A A A C C		1.4 1.4 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2 (04)1.2		3, 981 3, 981 3, 981 3, 189 3, 189
A924 A890		IX	(04)1, 2		3, 981 3, 501 3, 981
A891 A891 A890 A651	C A C	I I IV I	1. 4 1. 4 1. 4 (04)1. 2 1. 4	C E C	3, 981 3, 525 3, 525 3, 981 3, 981 3, 981
	A651 A651 A651 A659 A770 A791 A813 A814 A833 A834 A835 A836 A846 A865 A865 A866 A865 A866 A890 A892 A924 A891 A891 A891	DOD IC CLASS  A651 C A651 C A659 A A769 A A770 A A813 A A814 A A833 A A834 A A835 A A836 A A866 A A866 A A866 A A866 A A866 A A866 A A867 C C A924 A990 A A892 C A891 C A891 C A890 A A890 A A890 C A891 C A890 A A890 A A890 C A891 C A890 A A890 A A890 C C A891 C C A891 C C A890 A A890 A A890 C C A891 C C A890 A A890 C C A891 C C A890 A A890 C C A891 C C C A891 C C C C C C C C C C C C C C C C C C C	DOD   C	DOD IC	DOD IC

THIS APPENDIX SUPERSEDES THE TWO-LAYER UNITIZATION PROCEDURES OF INTERIM DRAWING 19-48-4141-20PA1003, DATED FEBRUARY 1977.

DO NOT SCALE

• HAZARD CLASSIFICATION DATA CONTAINED IN THE CHART AT LEFT IS FOR GUIDANCE AND INFORMATIONAL PURPOSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT JOINT HAZARD CLASSIFICATION SYSTEM LISTING OR OTHER APPROVED LISTING(S).

#### REVISIONS

REVISION NO. 1, DATED NOVEMBER 1981, CONSISTS OF:

- ADDING NATIONAL STOCK NUMBER TO THE "PALLET UNIT DATA" CHART.
- 4. REDESIGNING "FILLER ASSEMBLY".


REVISION NO. 2, DATED NOVEMBER 1982, CONSISTS OF: ADDING NOTE "J" TO GENERAL NOTES SECTION ON PAGE 2.

REVISION NO. 3, DATED DECEMBER 1983, CONSISTS OF:

1. CHANGING BOX DIMENSIONS.

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

Γ			REV	SIONS	*		WR	- /wi	
r		NOV BI	W.	D	1000 46 - 100	est/	W	anst	
L	_	MOV BI	WFE	John .	2 Bull		.,, -		^\./ <i>S</i>
ſ	2	NOV 82	18/2	2714	Thatta-rad	250	Henl	n/17	J <del>P</del> -3
┝	_	<b></b>	74	a) the	-75-I			- <del>-</del>	L. C. Aller
1	3	DEC 83	1/2E	CAL .	1 1 L	U. S.	ADAN F	ARCOM	DR MAINC
H	_	<u> </u>	<del>                                      </del>	2	الم مدرود	0. 3	JUN		DRAWING
					<del></del>	CLASS	2011	- 1501	794
Γ			7			10	40	4116/	20PA
L			$\angle$			19	48	15 <b>C</b>	1002



TOTAL WEIGHT

80 LBS

- 3,981 LAS (APPROX)

40.0 CU FT ( APPROX )


#### GENERAL NOTES

- A. THE APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-46-4116-20941002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THE APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THE APPENDIX.
- DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- STALL EACH HORIZONTAL STRAP TO ENCIRCUE EACH LAYER OF BOXES ON THE MALLET AND TO BE ALIGNED WITH THE HORIZONTAL PIECES OF THE "SUPPORT GATE" AS SHOWN, HORIZONTAL STRAPS MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE RALLET AND TO BE ALIGNED WITH THE VERTICAL PIECES OF THE "SUPPORT GATE" AS SHOWN. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING DAROOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.


- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ESUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING ZOMM CARTRIDGES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NIN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICIATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- J. REGARDLES OF THE QUANTITY OF BOXES TO BE PALLETIZED, THE TOTAL WEIGHT OF ANY MILLET UNIT WILL NOT BICEED 4,000 PCUNDS, WHEN THE TOTAL WEIGHT OF A FULLY LOADED PALLET UNIT BICEEDS 4,000 PCUNDS, ONE OR MORE LOADED BOXES MILST BE REMOVED, AND EITHER FILLER ASSEMBLIES, AS DEPICTED BELOW, OR EMPTY BOXES MILST BE SUBSTITUTED THEREFORE. FOR ADDITIONAL GUIDANCE, SEE THE "PROVISIONS FOR LESS-THAN-FULL-LAYB! LOADS" ON PAGE 5 OF THE BASIC UNITIZATION PROCEDURES DRAWING 19-40-4116-2004-1002.

	BILL OF MATERIAL					
LUMBER	LINEAR PEET	BOARD FEET				
1" X 4" 2" X 4"	14.00 19.00	5.33 19.00				
NAILS	NO, EQD	POUNDS				
64 (2°)	49	0,28				
STEEL STRAFFING SEAL FOR 1-1/4"	MILLET, 40" X 44"					

CUE --



( FOR MINUS ONE BOX )



MILLET -